



Outline

- Challenges in Implementing DfS
- Creating the IES-NUS DfS Library
- DfS Concepts
- Examples from DfS Library
- SafeSim Design Free Training

© Copyright National University of Singapore. All Rights Reserved.








Potential in	terventions to improve DfS	
Band I Training and development	 Continuing DfSP training and refresher courses DfS training for non-DfSP project stakeholders Samples and solutions 	
Band 2 Industry actions	 Incorporate Building Information Modelling (BIM) for DfS review Creating a DfSP association and having renewal criteria to maintain DfSP certification Recognition of good developers for DfS through awards 	
Band 3 Regulatory actions	 Submissions of the Risk Register to Ministry of Manpower (MOM) Compulsory 3rd party audits for DfS 	
© Copyright National University of Singapore. A	Rights Reserved.	





Existing DfS Libraries

Design for Safety (DfS) Library Examples of Hazards – Architectural Design



Design for Safety (DfS) Library Examples of Hazards – Mechanical & Electrical Design





Design for Safety (DfS)

Design for Safety (DfS) is the process where stakeholders of a construction project¹ come together at the earliest opportunity during different stages of a project² to identify and eliminate or reduce foreseeable design risks throughout the life cycle³ of a structure through good design.

Key Concepts


- . Reducing risk at source
- II. Collaborative and
 - systematic risk assessment
- III. Lifecycle approach


¹E.g., developer, designers, contractors

²From planning and design phases onwards

³E.g. construction, use/operation, demolition Adapted from https://www.tal.sg/wshc/Topics/Design-for-Safety/About-Design-for-Safety

© Copyright National University of Singapore. All Rights Reserved.





Would you review this hazard as part of DfS?



A prefabricated link bridge to be installed between two towers using welding; temporary corbels are provided. Due to the position of the joints, the welding is expected to take significant time.

13


14


© Copyright National University of Singapore. All Rights Reserved


13

Category A: Precast and Prefabrication Elements		
S/N:	A-4	
Design Consideration:	Prefabricated link bridge	
Context:	A prefabricated link bridge is to be installed between two towers using welding (see Figure 4); temporary corbels are provided. Due to the position of the joints, the welding is expected to take significant time.	
Design Risk:	The presence of the joints between the link bridge and the towers requires workers to work at height when welding the joints, and the extended exposure increases the likelihood of workers falling from height.	
Possible Incident:	Workers fall from height due to the need to work at height for an extended period.	
Possible Design- Related Control(s) or Change(s):	Substitution Design the connection between the bridge and the towers to use bolting instead of welding.	
Action By:	Architect, C&S Engineer	

 $\ensuremath{\textcircled{\sc 0}}$ Copyright National University of Singapore. All Rights Reserved.









Contractor's RA vs DfS Review

Contractor's Risk Assessment	DfS Review
Hazards identified based on work activities and locations	Hazards identified based on design elements and considerations
Controls are typically focused on lower rungs of the Hierarchy of Control (engineering control, administrative control, and personal protective equipment (PPE)) and Safe Work Procedures (SWP)	Controls are typically focused on higher rungs of the Hierarchy of Control (elimination, substitution, and engineering control)
Addresses the operations during the construction stage	Addresses the full life cycle of the structure, including construction stage
Focuses on what contractors can do to improve workplace safety and health	Focuses on what the designers can do to improve workplace safety and health

 $\ensuremath{\textcircled{\sc 0}}$ Copyright National University of Singapore. All Rights Reserved.





Category A: Precast	gory A: Precast and Prefabrication Elements		Note: Precast elements have obvious benefits in terms of speed and
s/N:	A-1		safety, but in this case, a partially cast-in-situ solution is selected because of the high risk of crane collapse.
Design Consideration:	Large and heavy prefabricated beams and columns that need to be lifted in place	Action By:	C&S Engineer, Architect
Context: The structure under construction is in the vicinity of sensitive structures (MRT/LRT viaduct). The site also has constraints that require the crane to be sited far from the structure where the prefabricated beam and columns must be installed. Thus, even the larger cranes need to operate at 95%-110% of the safe working load (SWL).		Full Section Beam	
Design Risk:	The presence of large and heavy precast beams and columns in the design that need to be lifted and installed in the vicinity of sensitive structures and the lifting radius is large. These design risks increase the likelihood of crane overload during construction.		
Possible Incident:	Workers struck by falling objects caused by inadequate crane load capacity.		Figure 1 Use u-shaped precast beams instead of full section beam
Possible Design- Related Control(s) or Change(s):	 Substitution Use U-shaped precast beams with cast-in-situ infill concrete to reduce the crane load (see Figure 1). Use precast shell columns with cast-in-situ infill concrete to reduce the crane load (see Figure 2). Considering the proximity to the sensitive structures, change selected precast elements to cast-in-situ to mitigate crane overload issues. 		Full Section Column "Shell" Column

Category D: Façade		
s/N:	D-1	
Design Consideration:	Installation of façade with protruding aluminium vertical fin at height (>3m)	
Context:	The façade of the building requires vertical aluminium fins to be manually installed on site.	KULLATA S
Design Risk:	The presence of a façade with long protruding aluminium vertical fins that need to be installed manually by workers on the gondola increases the likelihood of workers falling from height and falling objects during construction (see Figure 20).	Figure 20 Long protruding vertical fins that need to be installed manually by workers on a gondol
Possible Incident:	Fall from height when working on the gondola or struck by falling vertical fin.	1 2
Possible Design- Related Control(s) or Change(s):	Elimination Remove the fin design, if possible. Substitution 1. Design the fins to be part of the precast wall (see Figure 21). 2. Reduce the number and size of fins, if possible.	
Action By:	Architect, C&S Engineer	
		Figure 21 Vertical fins are prefabricated as part of the precast wall

 $\ensuremath{\mathbb{C}}$ Copyright National University of Singapore. All Rights Reserved.

egory F: Floor O	penings	
s/N:	F-1	
Design Consideration:	Permanent floor openings for M&E services	And Charter
Context:	Many floor openings (where construction workers can fall through) are protected with temporary covers such as planks and timber boards (see Figure 22) or uncovered.	
Design Risk:	The presence of many floor openings increases the likelihood of workers falling from height and being struck by falling object.	Figure 22 Floor openings with temporary covers such as planks and tir
Possible Incident:	The temporary cover used during construction may give way under the worker's weight or dislodge, resulting in the worker falling through. In addition, the unsafe covering can give a false sense of security to workers. If the openings are not covered, workers might fall into them accidentally.	
Possible Design- Related Control(s) or Change(s):	 Engineering Control Design for load-bearing mesh or pipe sleeves (if the services are smaller) to be cast in as part of the opening to protect workers once the opening is created (see Figure 23). However, the mesh will need to be cut away as services come through. An alternative is to bolt the mesh to the floor during construction. Then, remove the mesh when the services come through, but the opening is not guarded once the meshed is removed. 	
Action By:	C&S Engineer, Contractor	Figure 23 Cast load-bearing mesh as part of the opening

